THE CITY OF EDINBURG

ADDENDUM NUMBER THREE (3)

DATE: **June 6, 2013**

RE: **BID NO. 2013-84**

OWNER: **CITY OF EDINBURG**

TO: **ALL PROPOSERS, HOLDERS OF SPECIFICATIONS, AND ALL INTERESTED PARTIES TO THE CITY OF EDINBURG**

BID OPEN: **3:00 P.M. (Central Time), Monday, June 10, 2013 (*Revised by Addendum #1*)**

The following clarifications, corrections and directives shall become part of the Proposal, Contract Documents and Specifications for **BID No. 2013-84 – Manhole Rehabilitation Project.**

BID PROPOSAL FORM

1. Replace Bid Proposal Form, Pages C1-C5 with Revised Bid Proposal Form, Pages C1-C5 (SEE ATTACHMENTS).

CLARRIFICATION: The items description is include "Raven 405 epoxy coating (Or Approved Equal)". That is to include a **1"** cementitious material on both brick and concrete manholes.

Please make the necessary corrections to the Plans and Proposal, as appropriate.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED IN THE BID PROPOSAL FORM.

Approved by:

for

Ponciano N. Longoria, P.E., C.F.M.
Director of Public Works

Please direct your questions regarding the preparation of the bid to Mr. Ponciano Longoria, P.E., C.F.M. at (956) 388-8211.

Lorena Fuentes

Lorena Fuentes, Purchasing Agent

415 W. University Drive • P.O. Box 1079 • Edinburg, Texas 78540
Phone (956) 388-8204 • Fax (956) 383-7111

ADDENDUM #3
REVISED BID PROPOSAL FORM
MANHOLE REHABILITATION PROJECT
BID NO. 2013-84
EDINBURG, TEXAS

MR. PONCIANO N. LONGORIA, P.E., C.F.M.
DIRECTOR OF PUBLIC WORKS
CITY OF EDINBURG
415 W. UNIVERSITY DR.
EDINBURG, TEXAS 78539

The undersigned, as bidder(s), declares that the only person or parties interested in this proposal as principals are those named herein, that this proposal is made without collusion with any other person, firm or corporation; that he has carefully examined the Form of Contract, Notice to Bidders, General Conditions, Special Provisions, Measurement and Basis of Payment, specifications and the plans thereon referred to, and has carefully examined the locations, and conditions and classes of materials of the proposed work; and agrees that he will provide all the necessary labor, machinery, tools, and apparatus, and other items incidental to construction, and will do all the work and furnish all the materials called for in the contract and specifications in the manner prescribed therein and according to the requirements of the Engineer/Architect as therein set forth.

It is understood that the following quantities of work to be done at unit prices are approximate only and are intended principally to serve as a guide in evaluating bids.

It is further agreed that the quantities of work to be done at unit price and materials to be furnished, may be increased or diminished as may be considered necessary, in the opinion of the Engineer, to complete the work fully as planned and contemplated, and that all quantities of the work, whether increased or decreased, are to be performed at the unit prices set forth below except as provided for in the specifications.

It is further agreed that lump sum prices may be increased to cover additional work ordered by the Engineer, but not shown on the plans or required by the specifications, in accordance with the provisions of the General Conditions. Similarly, they may be decreased to cover deletion of work so ordered.

The 5% bid security accompanying this proposal shall be returned to the bidder, unless in case of the acceptance of the proposal the bidder shall fail to execute a contract and file a performance bond and payment bond within the ten (15) days after its acceptance, in which case the bid security shall become the property of the OWNER, and shall be considered as payment for damages due to delay and other inconveniences suffered by the Owner on account of such failure of the bidder. It is understood that the Owner reserves the right to reject any or all bids.

ORIGINAL BID PROPOSAL FORM MUST BE SUBMITTED ALONG WITH THE BID AND CONTRACT DOCUMENTS BOOKLET

BIDDERS BOND in the amount of $_____,(5%) of the greatest amount bid in compliance with the INSTRUCTION TO BIDDERS.

The above Cashiers Check or Bidder's Bond is to become the property of the City of Edinburg, Texas, in the event the construction contract (when offered by the Owner) and bonds are not executed within the time set forth.

IMPORTANT NOTE:
For information regarding the method UNIT ITEMS are to be MEASURED AND PAID, please refer to the "MEASUREMENT AND BASIS OF PAYMENT" Section attached and made part of this Proposal.

ESTIMATED QUANTITIES:

Item No.	Estimated Quantity	Unit	Item Description	Width & Depth	Bid Amount
1.	1	EA	**Brick - Manhole #1** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 18.5'	$_____
2.	1	EA	**Precast Concrete - Manhole #2** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 18.0'	$_____
3.	1	EA	**Precast Concrete - Manhole #3** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 13.8'	$_____
4.	1	EA	**Precast Concrete - Manhole #4** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 12.4'	$_____
5.	1	EA	**Precast Concrete - Manhole #5** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 12.1'	$_____
6.	1	EA	**Precast Concrete - Manhole #6** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 11.3'	$_____
7.	1	EA	**Precast Concrete - Manhole #7** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 7.3'	$_____
8.	1	EA	**Precast Concrete - Manhole #8** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 10.0'	$_____
9.	1	EA	**Precast Concrete - Manhole # 9** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 11.0'	$_____
10.	1	EA	**Precast Concrete - Manhole # 10** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 16.0'	$_____
11.	1	EA	**Precast Concrete - Manhole # 11** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 11.5'	$_____

12.	1	EA	**Precast Concrete - Manhole # 12** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 8.8'	$_____
13.	1	EA	**Precast Concrete - Manhole # 13** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 11.0'	$_____
14.	1	EA	**Precast Concrete - Manhole # 14** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 14.0'	$_____
15.	1	EA	**Precast Concrete - Manhole # 15** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 14.0'	$_____
16.	1	EA	**Precast Concrete - Manhole # 16** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 10.3'	$_____
17.	1	EA	**Precast Concrete - Manhole # 17** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 9.2'	$_____
18.	1	EA	**Precast Concrete - Manhole # 18** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 12.8'	$_____
19.	1	EA	**Precast Concrete - Manhole # 19** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 10.4'	$_____
20.	1	EA	**Precast Concrete - Manhole # 20** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 8.3'	$_____
21.	1	EA	**Precast Concrete - Manhole # 21** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 12.0'	$_____
22.	1	EA	**Precast Concrete - Manhole # 22** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	5' – 10.5'	$_____
23.	1	EA	**Brick - Manhole # 23** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 7.2'	$_____
24.	1	EA	**Brick - Manhole # 24** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 7.2'	$_____
25.	1	EA	**Brick - Manhole # 25** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 6.0'	$_____
26.	1	EA	**Brick - Manhole # 26** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 7.2'	$_____
27.	1	EA	**Brick - Manhole # 27** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 15.0'	$_____
28.	1	EA	**Precast Concrete - Manhole # 28** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 16.5'	$_____

29.	1	EA	**Precast Concrete - Manhole # 29** - Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 16.5'	$_____
30.	1	EA	**Precast Concrete - Manhole # 30** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 10.0'	$_____
31.	1	EA	**Precast Concrete - Manhole # 31** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 10.0'	$_____
32.	1	EA	**Brick - Manhole # 32** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 9.0'	$_____
33.	1	EA	**Brick - Manhole # 33** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 8.0'	$_____
34.	1	EA	**Brick - Manhole # 34** Raven 405 Epoxy (Or Approved Equal) with 1" Cementitious Material	4' – 7.0'	$_____

TOTAL: IMPROVEMENTS
(Items 1-34) $_____

The Number of Calendar days to complete contract **90 .**

The undersigned agrees, unless hereinafter stated otherwise to furnish all materials as shown and specified in the Plans and Specifications.

Bidder hereby agrees to commence work under this contract within 10 days after "NOTICE TO PROCEED" is issued, and to complete all the work in the Contract within **90 Calendar Days.**

The undersigned bidder acknowledges the receipt of the following addenda:

ADDENDUM NO.	DATE	BY
ADDENDUM No. 1		
ADDENDUM No. 2		
ADDENDUM No. 3		
ADDENDUM No. 4		
ADDENDUM No. 5		

Respectfully Submitted:

DATE:_____

BY:_____
(Signature)

_____
(Type or Print Name)

_____
(Title)

_____
(Company)

_____
(Address)

_____
(City, State, Zip)

_____
(Phone Number)

_____
(Fax Number)

(Seal – If Bidder is a Corporation)